

**SECTION 009112
ADDENDUM NUMBER 2**

PARTICULARS

1.01 DATE: AUGUST 30, 2023

**1.02 PROJECT: MIDLANDS TECHNICAL COLLEGE - STUDENT CENTER CHILLER
REPLACEMENT - AIRPORT CAMPUS.**

TO: PROSPECTIVE BIDDERS:

2.01 THIS ADDENDUM FORMS A PART OF THE CONTRACT DOCUMENTS AND MODIFIES THE ORIGINAL PROCUREMENT DOCUMENTS DATED AUGUST 1, 2023, WITH AMENDMENTS AND ADDITIONS NOTED BELOW.

2.02 ACKNOWLEDGE RECEIPT OF THIS ADDENDUM IN THE SPACE PROVIDED IN THE BID FORM. FAILURE TO DO SO MAY DISQUALIFY THE BIDDER.

2.03 THIS ADDENDUM CONSISTS OF 1 PAGE AND THE FOLLOWING ATTACHMENTS, SPECIFICATIONS, AND DRAWINGS:

CHANGES TO DRAWINGS:

3.01 DRAWING E1.0 - ELECTRICAL PLANS - DEMOLITION AND NEW WORK

- A. For each exterior chiller: Provide 2 #10, #10 grd. - 3/4"C. to new 30 amp./1p. breaker in existing 120/208v. panel located in the existing electrical room. Existing electrical room located adjacent to the existing loading dock. At each chiller, provide new heavy duty, fusible, safety switch, NEMA 3R. Connect heat tracing as directed by the equipment manufacturer.
- B. On each 30 amp. breaker feeding heat tracing, provide lock-on device to prevent breaker from being turned off. Provide labeling as specified.

END OF SECTION